
THIS DRAWING IS THE PROPERTY OF DG ARCHITECTURAL AND ENGINEERING FACILITY SOLUTIONS, PLLC AND SHALL NOT BE REPRODUCED, COPIED, LENT OR ALTERED DIRECTLY OR INDIRECTLY NOR USED FOR ANY PURPOSE OTHER THAN FOR WHICH IT IS SPECIFICALLY FURNISHED AND MUST BE RETURNED TO DG ARCHITECTURAL AND ENGINEERING FACILITY SOLUTIONS, PLLC ON COMPLETION OF WORK, IF REQUESTED.



1 M0.01 OVERALL FLOOR PLAN

1/16"=1'-0"

0 10 20

GENERAL NOTES

A. ALL DIMENSIONS AND MEASUREMENTS SHALL BE TAKEN FROM THE ARCHITECTURAL OR STRUCTURAL DRAWINGS AND SHALL BE VERIFIED IN THE FIELD.

B. DISCREPANCIES BETWEEN CIVIL, STRUCTURAL, ARCHITECTURAL, PLUMBING, ELECTRICAL, SPRINKLER, AND THESE DRAWINGS SHALL BE PROMPTLY BROUGHT TO THE ATTENTION OF THE GENERAL CONTRACTOR AND DESIGN GROUP (DG) PRIOR TO CONSTRUCTION.

C. MECHANICAL CONTRACTOR RESPONSIBLE TO COORDINATE ALL REQUIRED FLOOR, WALL, AND ROOF OPENINGS, SIZES, AND LOCATIONS WITH THE ARCHITECTURAL AND STRUCTURAL DRAWINGS. ANY DISCREPANCIES SHALL BE PROMPTLY BROUGHT TO THE ATTENTION OF THE GENERAL CONTRACTOR.

D. FIRE RATED AND NON-FIRE RATED FLOOR, WALL, AND ROOF PENETRATIONS SHALL BE SEALED PER APPLICABLE CONSTRUCTION DETAIL UNLESS OTHERWISE NOTED.

E. ALL ROOFTOP EQUIPMENT SHALL BE INSTALLED LEVEL OR IN ACCORDANCE WITH THE MANUFACTURER'S GUIDELINES.

F. ALL SUPPLY, RETURN, AND EXHAUST AIR DUCT (BOD) SHALL BE MOUNTED AS NOTED, ANY FIELD RELOCATION SHALL BE PROMPTLY BROUGHT TO THE ATTENTION OF THE ENGINEER. SEE HANGER AND SUPPORT DETAILS.

G. DUCTWORK ELBOWS SHALL BE LONG RADIUS OR SQUARE THROAT WITH FULL CURVATURE INTERNAL TURNING VANES. MITERED ELBOWS SHALL HAVE AIRFOIL TURNING VANES. ALL DUCTWORK ELBOWS SHALL BE FURNISHED AS SHOWN AND FABRICATED PER ASHRAE AND SMACNA STANDARDS.

H. ALL RECTANGULAR DUCTWORK VOLUME DAMPERS EXCEEDING 1 SQFT SHALL BE OPPOSED BLADE TYPE WITH MANUAL LOCKING OPERATORS PERIOD. SEE SPECIFICATIONS FOR ADDITIONAL REQUIREMENTS.

I. GRILLES AND DIFFUSERS WITH VOLUME DAMPERS LOCATED ABOVE INACCESSIBLE CEILINGS OR IN LOCATIONS WITHOUT PRACTICAL ACCESS SHALL BE CONTROLLED VIA REMOTE CONTROL BALANCING DAMPERS (GREENHECK MODEL RBDR-50 OR EQUIVALENT). CONTROLLER CONNECTION POINT SHALL BE LOCATED INSIDE GRILLE OR DIFFUSER UNLESS SPECIFIED OTHERWISE.

J. FLEXIBLE DUCT RUNOUTS SERVICING DIFFUSERS/REGISTERS SHALL NOT EXCEED 6'-0" IN LENGTH UNLESS OTHERWISE NOTED. WHERE FLEXIBLE DUCT IS USED AS A BEND OR ELBOW, THE INCLUDED ANGLE OR BEND SHALL NOT EXCEED 90 DEGREES IN ANY PLAN. ALL FLEXIBLE DUCT RUNOUTS SHALL BE INSTALLED TAUT WITHOUT EXCESSIVE SLACK OR OFFSETS AND SECURED AT EACH END WITH CLAMPING BANDS AS SPECIFIED.

K. ALL 24"X24" LAY-IN DIFFUSERS AND REGISTERS SHALL BE SUPPORTED BY THE CEILING GRID. FURNISH NECK SIZE AS SCHEDULED UNLESS OTHERWISE NOTED OR INDICATED BY THE CONNECTED DUCT SIZE.

L. ELECTRICAL CONTRACTOR SHALL PROVIDE 120V/1PH/60HZ POWER DEDICATED TO HVAC CONTROL PANELS. COORDINATE LOCATIONS WITH THE ELECTRICAL DRAWINGS. ATC SHALL DETERMINE CONNECTED CONTROL POWER LOAD REQUIREMENTS FOR EACH CIRCUIT UTILIZED, COORDINATE AND CONFIRM 120V/1PH/60HZ CIRCUIT CAPACITIES WITH THE GENERAL CONTRACTOR AND ELECTRICAL CONTRACTOR.

M. MECHANICAL CONTRACTOR SHALL RECEIVE SMOKE DETECTORS FROM THE ELECTRICAL CONTRACTOR FOR INSTALLATION, ATC RESPONSIBLE TO COORDINATE WIRING WITH ELECTRICAL CONTRACTOR PER SPECIFICATIONS.

N. COORDINATE ALL REQUIREMENTS FOR PROPOSED MECHANICAL EQUIPMENT SUBSTITUTIONS WITH OWNERS REPRESENTATIVE PRIOR TO SUBMISSION FOR ENGINEERS APPROVAL AND INSTALLATION. ALL CHANGE ORDERS GENERATED AS A RESULTS OF A MECHANICAL EQUIPMENT SUBSTITUTION SHALL BE THE RESPONSIBILITY OF THE MECHANICAL CONTRACTOR.

CODE SUMMARY

REFERENCE CODES:

2018	INTERNATIONAL BUILDING CODE
2018	INTERNATIONAL PLUMBING CODE
2018	INTERNATIONAL FUEL/GAS CODE
2018	INTERNATIONAL MECHANICAL CODE
2018	INTERNATIONAL FIRE CODE
2018	INTERNATIONAL COMMERCIAL ENERGY CODE
2017	NATIONAL ELECTRICAL CODE

ICC A117.1-2018 STANDARDS FOR ACCESSIBLE AND USABLE BUILDING AND FACILITIES

MECHANICAL LEGEND


- DEMOLISHED EQUIPMENT & PIPE
- EXISTING EQUIPMENT & PIPE
- BB — BOILER BLEED
- D — DRAIN FROM EQUIPMENT
- IV — COMBUSTION INTAKE
- EV — COMBUSTION EXHAUST
- G — NATURAL GAS
- G-2 — NATURAL GAS - 2 PSI
- G-5 — NATURAL GAS - 5 PSI
- G-10 — NATURAL GAS - 10 PSI
- CWR — COOLING WATER RETURN
- CWS — COOLING WATER SUPPLY
- HWR — HEATING HOT WATER RETURN
- HWS — HEATING HOT WATER SUPPLY
- RL — REFRIGERANT LIQUID
- RS — REFRIGERANT SUCTION
- GS — GLYCOL SUPPLY
- GR — GLYCOL RETURN
- STM — STEAM
- STM 15 — STEAM - 15 PSI
- STM 50 — STEAM - 50 PSI
- STM 100 — STEAM - 100 PSI
- HPC — CONDENSATE HIGH PRESSURE
- PC — CONDENSATE PUMPED
- CR — CONDENSATE RETURN
- SV — STEAM VENT
- BD — BOILER BLOWDOWN
- CHEM — BOILER CHEMICAL
- BFW — BOILER FEED
- BFT — BOILER FEED TRANSFER
- DIRECTION OF FLOW
- PIPE SLOPE
- PIPE PENETRATION
- FLEX PIPE CONNECTION
- TRI-CLAMP
- TEMPERATURE GAUGE IN WELL
- AIR VENT
- PRESSURE GAUGE (WITH AND WITHOUT PIGTAIL SIPHON)
- VACUUM BREAKER
- AUTOMATIC AIR VENT
- FLANGED CONNECTION
- UNION
- CONCENTRIC REDUCER
- ECCENTRIC REDUCER
- TEE CONNECTION UP
- TEE CONNECTION DOWN
- 90° ELBOW UP
- 90° ELBOW DOWN
- 45° ELBOW DOWN
- PIPE CAP
- PIPE BREAK
- ACTUATORS IN ORDER: DIAPHRAGM, ELECTRIC, HAND, HAND EXPANSION, HYDRAULIC
- ACTUATORS IN ORDER: MOTORIZED, PNEUMATIC, SOLENOID, WHEEL
- BALL VALVE
- 3-WAY BALL VALVE
- BUTTERFLY VALVE
- CHECK VALVE
- ANGLED STOP CHECK VALVE
- ANGLED GLOBE VALVE
- GATE VALVE
- 3-WAY GATE VALVE
- GLOBE VALVE
- OS&Y GATE VALVE
- PRESSURE REGULATING VALVE
- BALANCING VALVE
- TRIPLE-DUTY VALVE
- DIAPHRAGM VALVE
- ANGLE VALVE
- PLUG VALVE
- NEEDLE VALVE
- PIG VALVE
- STRAINER
- PRESSURE SAFETY RELIEF VALVE
- SENSOR PORT
- FLOW SWITCH
- GAS VALVE
- STEAM FLOW METER
- GENERIC FLOW METER
- WATER FLOW METER
- INVERTED BUCKET STEAM TRAP
- THERMODYNAMIC DISC STEAM TRAP
- PIPE ANCHOR
- DUCTWORK
- DUCT DOWN
- DUCT UP
- SHORT RADIUS ELBOW W/ TURNING VANES
- MITERED ELBOW W/ TURNING VANES
- CEILING SUPPLY DIFFUSER
- CEILING RETURN GRILLE
- CEILING EXHAUST GRILLE
- BELLMOUTH TAKEOFF
- 45° TAKEOFF
- FLEXIBLE CONNECTOR
- FLEX DUCT
- VOLUME DAMPER
- FIRE/SMOKE DAMPER
- MOTORIZED DAMPER
- DIRECTION OF AIRFLOW
- VVT SYSTEM CONTROLLER
- SMOKE DETECTOR
- STATIC PRESSURE SENSOR
- HUMIDISTAT
- THERMOSTAT
- TEMPERATURE SENSOR/ TRANSMITTER
- PROGRAMMABLE THERMOSTAT
- CARBON MONOXIDE SENSOR
- NITROGEN OXIDE SENSOR
- HYDROGEN SENSOR
- POINT OF CONNECTION (POC)
- POINT OF DEMOLITION (POD)
- US MATERIAL / DS MATERIAL — CHANGE OF MATERIAL
- TAG:CONNECTION AIRFLOW(CFM) — GRILLE/REGISTER/DIFFUSER TAG
- KEYNOTE
- # / M#.## — VIEW CALLOUT
- EQ # — NEW EQUIPMENT SYMBOL
- XXX / XXX / XXX — OFF-PAGE CONNECTOR
- XXX XXX / XXX XXX — SCOPE BREAK
- XXX XXX / XXX XXX — ROOM DELINEATION

MECHANICAL ABBREVIATIONS

AC	AIR COMPRESSOR	LDB	LEAVING DRY BULB
AHU	AIR HANDLING UNIT		TEMPERATURE
AFF	ABOVE FINISHED FLOOR	LFT	LEAVING FLUID TEMPERATURE
AMF	ABOVE MEZZANINE FLOOR	LRA	LOCKED ROTOR AMPS
AR	AIR ROTATION UNIT	LWB	LEAVING WET BULB
ARCU	AR CONDENSING UNIT		TEMPERATURE
ARS	ABOVE ROOF STRUCTURE	M	MOTORIZED OPERATOR
ASD	ADJUSTABLE SPEED DRIVE	MA	MAKEUP AIR UNIT
ATC	AUTOMATIC TEMPERATURE CONTROL	MBH	MBTU/HOUR
B.C.	BALANCING CONTRACTOR	M.C.	MECHANICAL CONTRACTOR
BOD	BOTTOM OF DUCT	MCA	MINIMUM CIRCUIT AMPS
CFM	CUBIC FEET PER MINUTE	MOCP	MAXIMUM OVER CURRENT
CF	CEILING FAN		PROTECTION
CH	CABINET HEATER	N.C.	NORMALLY CLOSED
CHU	CHILLER UNIT	N.O.	NORMALLY OPEN
C.M.	CONSTRUCTION MANAGER	NPT	NOMINAL PIPE THREAD
CO	CARBON MONOXIDE	OA	OUTSIDE AIR
DA	DEAERATOR TANK	P	PUMP
DBA	DECIBEL SOUND SCALE	P.C.	PLUMBING CONTRACTOR
DISC.	DISCONNECT	PD	PRESSURE DROP
DOAS	DEDICATED OUTDOOR AIR SYSTEM	PF	PERSONNEL FAN
DX	DIRECT EXPANSION	PFB	PARALLEL FAN BOX
EDB	ENTERING DRY BULB TEMPERATURE	PRV	PRESSURE REGULATING VALVE
EER	ENERGY EFFICIENCY RATIO	R	REGISTER/GRILLE
EF	EXHAUST FAN	RA	RETURN AIR
EFT	ENTERING FLUID TEMPERATURE	RCP	REFLECTED CEILING PLAN
EH	EXHAUST HOOD	RGD	REGISTER, GRILLE, AND/OR
EL	EXHAUST LOUVER		DIFFUSER
ESP	EXTERNAL STATIC PRESSURE	RL	REFRIGERATED LIQUID LINE
EUH	ELECTRIC HEATER	RS	REFRIGERATED SUCTION LINE
EV	EXHAUST VENT	RSD	REGISTER/GRILLE SMOKE
EWB	ENTERING WET BULB TEMPERATURE		DETECTOR
FCU	FAN COIL UNIT	RTU	ROOFTOP UNIT
FC	FLUID COOLER	SB	STEAM BOILER
FD	FIRE DAMPER	SCCR	SHORT CIRCUIT CURRENT RATING
FLA	FULL LOAD AMPS	SD	SMOKE DETECTOR
FP	FIRE PUMP	SEER	SEASONAL ENERGY EFFICIENCY
FPB	FAN-POWERED BOX		RATIO
FPI	FINS PER INCH	SF	SUPPLY FAN
FPM	FEET PER MINUTE	SFB	SERIES FAN BOX
FSD	COMBINATION FIRE/SMOKE DAMPER	SPK	SPRINKLER
G.C.	GENERAL CONTRACTOR	SSAU	SPLIT SYSTEM AIR UNIT
GUH	GAS UNIT HEATER	SSCU	SPLIT SYSTEM CONDENSING UNIT
HF	HANGING FAN	T	TRANSFER REGISTER
HOA	HAND/OFF/AUTO	TEV	THERMAL EXPANSION VALVE
HP	HORSEPOWER	TR	TEMPERATURE RISE
HVLS	HIGH-VOLUME LOW-SPEED FAN	TTD	TIGHT TO DECK
I	INTAKE	TTJ	TIGHT TO STRUCTURAL JOISTS
IEER	INTEGRATED ENERGY EFFICIENCY	V	VOLTS
	RATIO	VAV	VARIABLE AIR VOLUME
IH	INTAKE HOOD	VD	VOLUME DAMPER
IL	INTAKE LOUVER	VFD	VARIABLE FREQUENCY DRIVE
IV	INTAKE VENT	VRF	VARIABLE REFRIGERANT FLOW
KW	KILOWATT	VV	VALVE-OPERATED VAV BOX
LAT	LEAVING AIR TEMPERATURE	W	WATTS

MECHANICAL DRAWING LIST

M0.01	MECHANICAL OVERALL PLAN
M1.01	MECHANICAL ENLARGED FLOOR PLANS - AREA A
M1.02	MECHANICAL ENLARGED FLOOR PLANS - AREA B
M1.03	MECHANICAL ENLARGED FLOOR PLANS - AREA C
M2.01	MECHANICAL PIPING PLANS
M3.01	MECHANICAL AIR FLOW AND PIPING DIAGRAMS
M3.02	MECHANICAL PIPING ISOMETRICS - AREA C
M4.01	MECHANICAL SCHEDULES
M4.02	MECHANICAL SCHEDULES
M5.01	MECHANICAL DETAILS
M5.02	MECHANICAL DETAILS



KEY PLAN

DG Design Group
DG ARCHITECTURAL AND ENGINEERING FACILITY SOLUTIONS, PLLC
1075 WINDWARD RIDGE PKWY, STE 100, ALPHARETTA, GA 30005
PHONE: (770) 667-6250 FAX: (770) 667-6251

	DATE	BY	REVISION
1	08/17/2023	ACC	ISSUED FOR CONSTRUCTION

CLIENT: COCA-COLA BOTTLING CO. UNITED, INC. BIRMINGHAM, AL

PROJECT: NEW MCCOMB SALES CENTER MCCOMB, MS

DRAWING TITLE: MECHANICAL OVERALL PLAN

CONSTRUCTION DOCUMENTS — NOT FOR CONSTRUCTION — PRELIMINARY — NOT FOR BIDDING — NOT FOR PERMIT — NOT FOR REGULATORY APPROVAL — NOT FOR RECORDING — NOT FOR GOVERNMENTAL APPROVAL — ENGINEER 34021

PROJECT NO.	2102482
ISSUED	08/11/23
SCALE	AS NOTED
DRAWN BY	KCC

DRAWING NO.

M0.01

© 2022 DG ARCHITECTURAL AND ENGINEERING FACILITY SOLUTIONS, PLLC

DATE PLOTTED:8/11/2023 11:51:32 AM

THIS DRAWING IS THE PROPERTY OF DG ARCHITECTURAL AND ENGINEERING FACILITY SOLUTIONS, PLLC AND SHALL NOT BE REPRODUCED, COPIED, LENT OR ALTERED DIRECTLY OR INDIRECTLY NOR USED FOR ANY PURPOSE OTHER THAN FOR WHICH IT IS SPECIFICALLY FURNISHED AND MUST BE RETURNED TO DG ARCHITECTURAL AND ENGINEERING FACILITY SOLUTIONS, PLLC ON COMPLETION OF WORK, IF REQUESTED

KEYNOTES

1 SUPPORT HEATER FROM GIRDER PER DETAIL 5/M5.01. MOUNT AT 12'-0" AFF.
2 PLENUM SIZE SHALL MATCH LOUVER. PLENUM SHALL BE MINIMUM 18" DEEP.
3 MOUNT TEMPERATURE SENSOR FOR EXHAUST FAN ON WALL BELOW EXHAUST FAN AT 12'-0" ABOVE FINISH FLOOR.
4 INSTALL BOTTOM OF LOUVER AT 11'-0" ABOVE FINISH FLOOR. COORDINATE FINAL LOCATION WITH STRUCTURE.
5 EXHAUST FAN LOCATED UPON LOW ROOF OF PART ROOM.
6 HIGH VOLUME LOW SPEED FAN TO BE PLACED BETWEEN FOUR ADJACENT SPRINKLER HEADS. LOCATIONS SHOWN ARE APPROXIMATE. CONFIRM FINAL LOCATION IN COORDINATION WITH STRUCTURAL AND FIRE PROTECTION CONTRACTORS.
7 INSTALL BOTTOM OF LOUVER AT 16'-0" ABOVE FINISH FLOOR. COORDINATE FINAL LOCATION WITH STRUCTURE.
8 PERSONNEL FAN TO BE MOUNTED AT 7'-6" AFF.
9 CAMBRIDGE AIR SYSTEM HEATER TO BE SUPPORTED FROM ROOF STRUCTURE. BOTTOM OF UNIT TO BE AT 16'-3 1/2" ABOVE FINISH FLOOR.
10 BAFCON CONTROLLER FOR HVLS-2. SEE M5.02 FOR CONTROLS DIAGRAM. FINAL LOCATION MUST BE APPROVED BY DESIGN GROUP REPRESENTATIVE OR OWNER PRIOR TO INSTALLATION.
11 ANCHOR UNIT TO CONCRETE PAD ON GRADE OUTDOORS. PAD SHALL BE A MINIMUM OF 3" LARGER THAN FOOTPRINT OF EQUIPMENT ON ALL SIDES AND 6" TALL. INSTALL UNIT WITH SUCTION SIDE FACING EXTERIOR WALL TO PREVENT EXPOSURE TO WIND. ROUTE REFRIGERANT PIPING, SIZED PER MANUFACTURER'S RECOMMENDATIONS, FROM UNIT UP EXTERIOR WALL INTO BUILDING ABOVE CEILING. PROVIDE SHEET METAL COVER FOR PIPING ALONG WALL.

SIDE LOAD
500

FLEET MAINT.
400

FLEET OFFICE
401

PARTS
301

VENDING REPAIR & STORAGE
300

VENDING OFFICE
302

POS AREA
203

WAREHOUSE
200

SEE M5.02 FOR CONTROLS DIAGRAM.

SEE CIVIL FOR EVELATION & CONTINUATION

B: 14"x6" 400 CFM

B: 12"ø 375

A: 10"ø 400

12"x12" RA

16"x12" RA

16"x12" RA

14"x10" SA

1 1/2"ø G-2

SOP: 22'-10"

1"ø G-2

MATCHLINE 1 / M1.02

1 M1.01 ENLARGED MECHANICAL FLOOR PLANS - AREA A
3/16"=1'-0"
0 1 2 3 4 5 10

AREA A

KEY PLAN

N PROJECT NORTH

DATE PLOTTED: 1/12/2024 11:21:23 AM

DG Design Group
DG ARCHITECTURAL AND ENGINEERING FACILITY SOLUTIONS, PLLC
1075 WINDWARD RIDGE PKWY, STE 100, ALPHARETTA, GA 30005
PHONE: (770) 667-6250 FAX: (770) 667-6251

	BY	DATE	REVISION
1	KCC	08/11/2023	ISSUED FOR CONSTRUCTION
2	KCC	01/12/2024	BULLETIN 1

CLIENT: COCA-COLA BOTTLING CO. UNITED, INC. BIRMINGHAM, AL
PROJECT: NEW MCCOMB SALES CENTER MCCOMB, MS
DRAWING TITLE: MECHANICAL ENLARGED FLOOR PLANS – AREA A

DONALD R HARTSOCK ENGINEER 34021 STATE OF MISSISSIPPI LICENSED PROFESSIONAL ENGINEER


PROJECT NO. 2102482
ISSUED 08/11/23
SCALE AS NOTED
DRAWN BY KCC
DRAWING NO. M1.01

© 2022 DG ARCHITECTURAL AND ENGINEERING FACILITY SOLUTIONS, PLLC

THIS DRAWING IS THE PROPERTY OF DG ARCHITECTURAL AND ENGINEERING FACILITY SOLUTIONS, PLLC AND SHALL NOT BE REPRODUCED, COPIED, LENT OR ALTERED DIRECTLY OR INDIRECTLY NOR USED FOR ANY PURPOSE OTHER THAN THAT FOR WHICH IT IS SPECIFICALLY FURNISHED AND MUST BE RETURNED TO DG ARCHITECTURAL AND ENGINEERING FACILITY SOLUTIONS, PLLC ON COMPLETION OF WORK, IF REQUESTED.

KEYNOTES


1. MOUNT TEMPERATURE SENSOR FOR EXHAUST FAN ON WALL BELOW EXHAUST FAN AT 12'-0" ABOVE FINISH FLOOR.
2. HIGH VOLUME LOW SPEED FAN TO BE PLACED BETWEEN FOUR ADJACENT SPRINKLER HEADS. LOCATIONS SHOWN ARE APPROXIMATE. CONFIRM FINAL LOCATION IN COORDINATION WITH STRUCTURAL AND FIRE PROTECTION CONTRACTORS.
3. INSTALL BOTTOM OF LOUVER AT 16'-0" ABOVE FINISH FLOOR. COORDINATE FINAL LOCATION WITH STRUCTURE.
4. PLENUM SIZE SHALL MATCH LOUVER. PLENUM SHALL BE MINIMUM 18" DEEP.
5. CAMBRIDGE AIR SYSTEM HEATER TO BE SUPPORTED FROM ROOF STRUCTURE. BOTTOM OF UNIT TO BE AT 16'-3 1/2" ABOVE FINISH FLOOR.



1 M1.02 ENLARGED MECHANICAL FLOOR PLANS - AREA B

3/16"=1'-0"

0 1 2 3 4 5 10



KEY PLAN

DG Design Group
DG ARCHITECTURAL AND ENGINEERING FACILITY SOLUTIONS, PLLC
1075 WINDWARD RIDGE PKWY, STE 100, ALPHARETTA, GA 30005
PHONE: (770) 667-6250 FAX: (770) 667-6251

	BY	DATE	REVISION
1	KCC	08/11/2023	ISSUED FOR CONSTRUCTION BULLETIN 1

CLIENT: COCA-COLA BOTTLING CO. UNITED, INC. BIRMINGHAM, AL

PROJECT: NEW MCCOMB SALES CENTER MCCOMB, MS

DRAWING TITLE: MECHANICAL ENLARGED FLOOR PLANS – AREA B

DONALD R. HARTSFIELD, 23021, ENGINEER, STATE OF MISSISSIPPI

PROJECT NO.	2102482
ISSUED	08/11/23
SCALE	AS NOTED
DRAWN BY	KCC

DRAWING NO. M1.02


© 2022 DG ARCHITECTURAL AND ENGINEERING FACILITY SOLUTIONS, PLLC

DATE PLOTTED:1/12/2024 11:21:27 AM

THIS DRAWING IS THE PROPERTY OF DG ARCHITECTURAL AND ENGINEERING FACILITY SOLUTIONS, PLLC AND SHALL NOT BE REPRODUCED, COPIED, LENT OR ALTERED DIRECTLY OR INDIRECTLY NOR USED FOR, ANY PURPOSE OTHER THAN THAT FOR WHICH IT IS SPECIFICALLY FURNISHED AND MUST BE RETURNED TO DG ARCHITECTURAL AND ENGINEERING FACILITY SOLUTIONS, PLLC ON COMPLETION OF WORK, IF REQUESTED.

KEYNOTES


1. ANCHOR UNIT TO CONCRETE PAD ON GRADE OUTDOORS. PAD SHALL BE A MINIMUM OF 3" LARGER THAN FOOTPRINT OF EQUIPMENT ON ALL SIDES AND 6" TALL. INSTALL UNIT WITH SUCTION SIDE FACING EXTERIOR WALL TO PREVENT EXPOSURE TO WIND. ROUTE REFRIGERANT PIPING, SIZED PER MANUFACTURER'S RECOMMENDATIONS, FROM UNIT UP EXTERIOR WALL INTO BUILDING ABOVE CEILING. PROVIDE SHEET METAL COVER FOR PIPING ALONG WALL.
2. DUCT PENETRATION THRU FULL-HEIGHT WALL. FRAMING BY OTHERS; COORDINATE WITH ARCHITECTURAL.
3. ALL OUTSIDE DUCTWORK SHALL BE DOUBLE WALL WITH 2" FIBERGLASS INSULATION.
4. FINAL LOCATION OF THERMOSTAT TO BE COORDINATED WITH LOW VOLTAGE / ELECTRICAL CONTRACTOR (TYPICAL).
5. PLENUM SIZE SHALL MATCH LOUVER. PLENUM SHALL BE MINIMUM 18" DEEP.
6. INSTALL BOTTOM OF LOUVER AT 16'-0" ABOVE FINISH FLOOR. COORDINATE FINAL LOCATION WITH STRUCTURE.
7. MOUNT TEMPERATURE SENSOR FOR EXHAUST FAN ON WALL BELOW EXHAUST FAN AT 12'-0" ABOVE FINISH FLOOR.
8. BAFCON CONTROLLER FOR HVLS-3, 4, 5. SEE M5.02 FOR CONTROLS DIAGRAM. FINAL LOCATION MUST BE APPROVED BY DESIGN GROUP REPRESENTATIVE OR OWNER PRIOR TO INSTALLATION.



1 M1.03 ENLARGED MECHANICAL FLOOR PLANS - AREA C

3/16"=1'-0"

0 1 2 3 4 5 10



KEY PLAN

DG Design Group
DG ARCHITECTURAL AND ENGINEERING FACILITY SOLUTIONS, PLLC
1075 WINDWARD RIDGE PKWY, STE 100, ALPHARETTA, GA 30005
PHONE: (770) 667-6250 FAX: (770) 667-6251

	BY	DATE	REVISION
1	KCC	08/11/2023	ISSUED FOR CONSTRUCTION

CLIENT: COCA-COLA BOTTLING CO. UNITED, INC. BIRMINGHAM, AL

PROJECT: NEW MCCOMB SALES CENTER MCCOMB, MS

DRAWING TITLE: MECHANICAL ENLARGED FLOOR PLANS – AREA C

PROJECT NO.	2102482
ISSUED	08/11/23
SCALE	AS NOTED
DRAWN BY	KCC
DRAWING NO.	M1.03


© 2022 DG ARCHITECTURAL AND ENGINEERING FACILITY SOLUTIONS, PLLC

DATE PLOTTED:8/11/2023 11:51:40 AM

THIS DRAWING IS THE PROPERTY OF DG ARCHITECTURAL AND ENGINEERING FACILITY SOLUTIONS, PLLC AND SHALL NOT BE REPRODUCED, COPIED, LENT OR ALTERED DIRECTLY OR INDIRECTLY NOR USED FOR ANY PURPOSE OTHER THAN THAT FOR WHICH IT IS SPECIFICALLY FURNISHED AND MUST BE RETURNED TO DG ARCHITECTURAL AND ENGINEERING FACILITY SOLUTIONS, PLLC ON COMPLETION OF WORK, IF REQUESTED.

KEYNOTES


1. ANCHOR UNIT TO CONCRETE PAD ON GRADE OUTDOORS. PAD SHALL BE A MINIMUM OF 3" LARGER THAN FOOTPRINT OF EQUIPMENT ON ALL SIDES AND 6" TALL. INSTALL UNIT WITH SUCTION SIDE FACING EXTERIOR WALL TO PREVENT EXPOSURE TO WIND. ROUTE REFRIGERANT PIPING, SIZED PER MANUFACTURER'S RECOMMENDATIONS, FROM UNIT UP EXTERIOR WALL INTO BUILDING ABOVE CEILING. PROVIDE SHEET METAL COVER FOR PIPING ALONG WALL.
2. SEE M3.01 FOR REFRIGERANT PIPING DIAGRAM.
3. SSCU-3 SHALL BE MULTI-ZONE UNIT USING CARRIER ZONING KIT OR EQUIVALENT WITH MINIMUM CAPACITY OF FOUR ZONES.
4. INSULATE MECHANICAL EQUIPMENT CONDENSATE DRAIN PIPING WITH 1"-THICK FLEXIBLE ELASTOMERIC INSULATION (TYPICAL).
5. DRAIN LINE IN WALL FROM PUMP. PUMP - LITTLE GIANT: MODEL NO. VCCA-20ULS, 1/30 HP, VOLTAGE 115. PUMP MOUNTED IN WALL WITH ACCESS DOOR FLUSH WITH FINISHED WALL. INSTALL CLEANOUT AS REQUIRED.
6. PROVIDE 1 1/2"-DEEP, GALVANIZED AUXILIARY DRAIN PAN. DRAIN PAN SHALL EXTEND 1 1/2" INCHES BEYOND OUTER EDGES OF UNIT. PROVIDE FLOAT SWITCH IN DRAIN PAN TO SHUT DOWN EQUIPMENT UPON ACTIVATION.
7. 2" CONDENSATE DRAIN PIPE DOWN INSIDE OF WALL. TERMINATE AT THE FLOOR.
8. REFRIGERATION PIPING SHOWN IS THE PREFERRED RECOMMENDED PATH WITH ALL MAIN REFRIGERANT PIPING TO BE ROUTED IN THE COORIDORS AND COMMON AREAS. CONTRACTOR SHALL COORDINATE WITH OTHER TRADES TO ENSURE ACCESSABILITY. CONTRACTOR SHALL PROVIDE A PIPING SHOP DRAWING FOR REVIEW PRIOR TO INSTALLATION.
9. ENSURE ALL CONDENSATE LINES PITCH DOWN MINIMUM 1/8" PER FOOT.
10. REFRIGERANT PIPING SHALL BE INSTALLED ALONG VERTICAL CONCRETE RAIL FOOTING FROM BUILDING TO CONDENSING UNIT.



1 M2.01 MECHANICAL VRF PIPING PLAN - AREA C

3/16"=1'-0"

0 1 2 3 4 5 10



KEY PLAN

N PROJECT NORTH

DG Design Group
DG ARCHITECTURAL AND ENGINEERING FACILITY SOLUTIONS, PLLC
1075 WINDWARD RIDGE PKWY, STE 100, ALPHARETTA, GA 30005
PHONE: (770) 667-6250 FAX: (770) 667-6251

	BY	DATE	REVISION
A	KCC	08/11/2023	ISSUED FOR CONSTRUCTION

CLIENT: COCA-COLA BOTTLING CO. UNITED, INC. BIRMINGHAM, AL

PROJECT: NEW MCCOMB SALES CENTER MCCOMB, MS

DRAWING TITLE: MECHANICAL PIPING PLANS

PROJECT NO. 2102482
ISSUED 08/11/23
SCALE AS NOTED
DRAWN BY KCC


DRAWING NO.

M2.01


© 2022 DG ARCHITECTURAL AND ENGINEERING FACILITY SOLUTIONS, PLLC

DATE PLOTTED:8/11/2023 11:51:43 AM


THIS DRAWING IS THE PROPERTY OF DG ARCHITECTURAL AND ENGINEERING FACILITY SOLUTIONS, PLLC AND SHALL NOT BE REPRODUCED, COPIED, LENT OR ALTERED DIRECTLY OR INDIRECTLY NOR USED FOR ANY PURPOSE OTHER THAN FOR WHICH IT IS SPECIFICALLY FURNISHED AND MUST BE RETURNED TO DG ARCHITECTURAL AND ENGINEERING FACILITY SOLUTIONS, PLLC ON COMPLETION OF WORK, IF REQUESTED.



1 M3.01 AIR FLOW DIAGRAM - MAIN OFFICE
NTS



THIS DRAWING IS THE PROPERTY OF DG ARCHITECTURAL AND ENGINEERING FACILITY SOLUTIONS, PLLC AND SHALL NOT BE REPRODUCED, COPIED, LENT OR ALTERED DIRECTLY OR INDIRECTLY NOR USED FOR ANY PURPOSE OTHER THAN FOR WHICH IT IS SPECIFICALLY FURNISHED AND MUST BE RETURNED TO DG ARCHITECTURAL AND ENGINEERING FACILITY SOLUTIONS, PLLC ON COMPLETION OF WORK, IF REQUESTED.



1 M3.02 NATURAL GAS PIPING ISOMETRIC
NTS

Design Group
DG ARCHITECTURAL AND ENGINEERING FACILITY SOLUTIONS, PLLC
1075 WINDWARD RIDGE PKWY, STE 100, ALPHARETTA, GA 30005
PHONE: (770) 667-6250 FAX: (770) 667-6251

	DATE	BY	REVISION
1	08/11/2023	KCC	ISSUED FOR CONSTRUCTION

CLIENT: COCA-COLA BOTTLING CO. UNITED, INC. BIRMINGHAM, AL
PROJECT: NEW MCCOMB SALES CENTER MCCOMB, MS
DRAWING TITLE: MECHANICAL PIPING ISOMETRICS - AREA C

PROJECT NO. 2102482
ISSUED 08/11/23
SCALE AS NOTED
DRAWN BY KCC
DRAWING NO.
M3.02

© 2022 DG ARCHITECTURAL AND ENGINEERING FACILITY SOLUTIONS, PLLC

DATE PLOTTED:8/11/2023 11:51:45 AM

NATURAL GAS DEMAND SCHEDULE

EQ. TAG	UNIT DESCRIPTION	UNIT LOCATION	MBH	REQUIRED INLET PRESSURE
GUH-1	GAS UNIT HEATER	WAREHOUSE	250	5 PSI MAXIMUM
GUH-2	GAS UNIT HEATER	WAREHOUSE	250	5 PSI MAXIMUM
DOAS-1	DEDICATED OUTSIDE AIR SYSTEM	MECHANICAL YARD	75	0.5 PSI
TOTAL CONNECED LOAD: 575 MBH = 75 CFH @ 2 PSI				
TOTAL DEVELOPED LENGTH FROM METER TO REMOTE REGULATOR (LINEAR FEET): 1100'				
GAS PIPING SIZED BASED ON 2021 INTERNATIONAL FUEL GAS CODE - GAS PIPING TABLES				

FAN SCHEDULE — EF

GENERAL				FAN MOTOR						UNIT DATA		ELECTRICAL			
EQ. TAG	SERVICE	MFR	MODEL	FAN AIRFLOW (CFM)	FAN SPEED (RPM)	E.S.P. (IN. W.C.)	BRAKE HP (HP)	MOTOR POWER (HP)	DRIVE	INLET SOUND (dBA)	WT (LB.)	ROOF/WALL OPENING (IN. X IN.)	DISCONNECT	V/HZ/PH	CONTROLS	REMARKS
EF-1	PARTS	GREENHECK	CUE-100HP-VG	400	1396	0.5	0.1	1/4	DIRECT	51	47	15.5" X 15.5"	NEMA 1; PROVIDED BY MFR	115/60/1		
EF-2	POS AREA	GREENHECK	AER-E24C-420-VG	4000	1006	0.20	0.30	3/4	DIRECT	68	154	33.75" X 33.75"	NEMA 1; PROVIDED BY MFR	277/60/1	NOTE 9	1, 2, 3, 4, 5
EF-3	WAREHOUSE	GREENHECK	AER-E24C-420-VG	4000	1006	0.20	0.30	3/4	DIRECT	68	154	33.75" X 33.75"	NEMA 1; PROVIDED BY MFR	277/60/1	NOTE 9	1, 2, 3, 4, 5
EF-4	WAREHOUSE	GREENHECK	AER-E24C-420-VG	4000	1006	0.20	0.30	3/4	DIRECT	68	154	33.75" X 33.75"	NEMA 1; PROVIDED BY MFR	277/60/1	NOTE 9	1, 2, 3, 4, 5
EF-5	REST ROOMS / BREAK ROOM	GREENHECK	CSP-A700-VG	650	1218	0.5	N/A	143W	DIRECT	34	40	N/A	PLUG TYPE	115/60/1	NOTE 10	6, 7, 8
EF-6	FLEET MAINT.	GREENHECK	SE2-18-411-A	1791	1750	0.59	0.34	1/2	DIRECT	76	49	20.5" X 20.5"	NEMA 1; PROVIDED BY MFR	115/60/1	NOTE 9	1, 2, 3, 4, 5

NOTES:
1. DIRECT DRIVE PROPELLER SIDEWALL EXHAUST FAN WITH AIRFOIL BLADES.
2. 115-VAC ACTUATED BACKDRAFT DAMPER WITH END SWITCH.
3. PROVIDE WITH WALL COLLAR.
4. PROVIDE WITH OSHA APPROVED MESH FAN SAFETY GUARD INTERIOR.
5. 1/2" X 1/2" ALUMINUM BIRD SCREEN.
6. INLINE CABINET FAN
7. GALVANIZED STEEL HOUSING WITH ALUMINUM BLADES.
8. SOUND ABSORBING INSULATION.
9. TEMPERATURE SENSOR IN SPACE AND 1-SPEED CONTROLLER.
10. SOLID STATE SPEED CONTROL, 7 AMP.

SPLIT SYSTEM INDOOR UNIT SCHEDULE (PURCHASED BY OWNER) — SSAU

GENERAL				SUPPLY AIR			COOLING					HEATING			UNIT DATA					ELECTRICAL				
EQ. TAG	AREA SERVED	MFR	MODEL	SUPPLY AIR (CFM)	OUTSIDE AIR (CFM)	E.S.P. (IN. W.C.)	COOLING MEDIUM	EAT DB/WB (°F)	LAT DB/WB (°F)	SENSIBLE CAPACITY (BTU/H)	TOTAL CAPACITY (BTU/H)	EAT (°F)	LAT (°F)	MAX. HEATING CAPACITY (BTU/H)	L (IN.)	W (IN.)	H (IN.)	WT (LB)	FILTER	DISC.	V/HZ/PH	MCA/ MOCP	CONTROLS	REMARKS
SSAU-1	FLEET OFFICE	CARRIER (NO EXCEPTIONS)	40MBDQ18---3	400	25	0.00	R410A	80.0/67.0	54.1	16500	18800	70.0	103	21500	35	14	29	101	MERV-8	BY MFR	208-230/60/1	16 / 25	THERMOSTAT IN SPACE	NOTES 1 THRU 4. PIPE TO SSCU-1 PER MANUFACTURER'S RECOMMENDATIONS.
SSAU-2	VENDING OFFICE	CARRIER (NO EXCEPTIONS)	40MBDQ18---3	400	25	0.00	R410A	80.0/67.0	54.1	16500	18800	70.0	103	21500	35	14	29	101	MERV-8	BY MFR	208-230/60/1	16 / 25	THERMOSTAT IN SPACE	NOTES 1 THRU 4. PIPE TO SSCU-2 PER MANUFACTURER'S RECOMMENDATIONS.

NOTES:
1. DUCTED INDOOR UNIT.
2. BUILT-IN CONDENSATE PUMP.
3. HANDHELD, WIRELESS THERMOSTAT REMOTE.
4. EQUIPMENT WILL BE FURNISHED BY OWNER. THE CONTRACTOR SHALL ASSUME OWNERSHIP OF THE EQUIPMENT AS A PART OF THE CONTRACT INCLUDING POSSESSION ON SITE, HANDLING, STORAGE, INSTALLATION, STARTUP, AND WARRANTY.

SPLIT SYSTEM OUTDOOR UNIT SCHEDULE (PURCHASED BY OWNER) — SSCU

GENERAL						PERFORMANCE DATA					UNIT DATA				ELECTRICAL				
EQ. TAG	EQUIPMENT SERVED	MFR	MODEL	COMPRESSOR TYPE	COOLING MEDIUM	COOLING CAPACITY (BTU/H)	HP HEATING CAPACITY (BTU/H)	MINIMUM EFFICIENCY RATING	SOUND LEVEL (DBA)	L (IN.)	W (IN.)	H (IN.)	WT. (LB)	FAN POWER (W)	DISC.	V/HZ/PH	MCA/ MOCP	REMARKS
SSCU-1	SSAU-2	CARRIER (NO EXCEPTIONS)	38MARBQ18AA3	ROTARY	R410A	15875	14268	22.3 SEER	56	35	14	29	101	20	BY MFR	208-230/60/1	16 / 25	1, 2, 3, 4, 5
SSCU-2	SSAU-1	CARRIER (NO EXCEPTIONS)	38MARBQ18AA3	ROTARY	R410A	15875	14268	22.3 SEER	56	35	14	29	101	20	BY MFR	208-230/60/1	16 / 25	1, 2, 3, 4, 5
SSCU-3	FS-1 THRU FS-5	CARRIER (NO EXCEPTIONS)	MMY-AP1926FT6P-UL	ROTARY	R410A	182012	151019	23.3 IEER	65	95	31	73	1368	1kW + 1kw	BY MFR	460/60/3	17+17 / 20+20	NOTE 5. DUAL 8-TON MODULES COMBINED TO FORM 16-TON HEAT RECOVERY SYSTEM. VARIABLE REFRIGERANT FLOW AIR-COOLED CONDENSING UNIT.

NOTES:
1. AIR-COOLED HEAT PUMP CONDENSING UNIT.
2. REFRIGERANT BASE CHARGE - 2.1LB.
3. MINIMUM AMBIENT TEMPERATURES: 50°F DB IN COOLING, 5°F WB IN HEATING.
4. SINGLE COMPRESSOR UNIT.
5. EQUIPMENT WILL BE FURNISHED BY OWNER. THE CONTRACTOR SHALL ASSUME OWNERSHIP OF THE EQUIPMENT AS A PART OF THE CONTRACT INCLUDING POSSESSION ON SITE, HANDLING, STORAGE, INSTALLATION, STARTUP, AND WARRANTY.

DOAS UNIT SCHEDULE (PURCHASED BY OWNER) — DOAS

GENERAL			UNIT DATA								HEATING DATA					ELECTRICAL DATA		
EQ. TAG	MFR	MODEL	UNIT SIZE	L (IN.)	W (IN.)	H (IN.)	WT (LB.)	E.S.P (in. W.C.)	AIRFLOW (CFM)	COOLING EAT °F (DB/WB)	COOLING LAT °F DB/WB	HEATING EAT (°F)	HEATING LAT (°F)	HEATING INPUT (MBH)	HEATING OUTPUT (MBH)	BURNER EFFICIENCY (%)	V/HZ/PH	MCA/MOCP	REMARKS
DOAS-1	CARRIER (NO EXCEPTIONS)	62XE07-AJT-JH2--LM	07 (7 TONS)	9'-7"	5'-4"	5'-0"	1750	1	1000	81.7/ 77	52.6/52.6	23	86.3	75	60	80	460/60/3	36 / 40	NOTE 1. UNIT PARAMETERS: CONFIGURATION: 100% OA HORIZONTAL SUPPLY, CABINET:-A, 6 ROW EVAPORATOR, 2" MERV 8 FILTERS

NOTES:
1. EQUIPMENT WILL BE FURNISHED BY OWNER. THE CONTRACTOR SHALL ASSUME OWNERSHIP OF THE EQUIPMENT AS A PART OF THE CONTRACT INCLUDING POSSESSION ON SITE, HANDLING, STORAGE, INSTALLATION, STARTUP, AND WARRANTY.

ROOF EXHAUST HOOD SCHEDULE — EH

EQ. TAG	AREAS SERVED	MFR	MODEL	MODEL SIZE (IN.)	CURB CAP DIMENSIONS	UNIT HEIGHT (IN)	WEIGHT (LBS)	ROOF OPENING	AIRFLOW (CFM)	SP (IN. W.C.)	THROAT AREA (FT2)	THROAT VELOCITY (FT/MIN)	REMARKS
EH-1	RESTROOMS, BREAKROOM	GREENHECK	GRSR-12	12	22" X 22"	22	10	14.5" X 14.5"	650	0.08	1	793	1, 2, 3

1. ALUMINUM HOUSING.
2. ALUMINUM CURB CAP WITH PREPUNCHED MOUNTING HOLES.
3. RECOMMENDED ROOF OPENING DIMENSION IS AT LEAST 2.5 IN. LARGER THAN THE DAMPER SIZE.

VRF SCHEDULE (PURCHASED BY OWNER) — VRF

GENERAL						COOLING			HEATING			ELECTRICAL		
EQ. TAG	AREA SERVED	MFR	MODEL	CFM	MOTOR WATTS	EAT (DB/WB)	SENSIBLE (BTUH)	TOTAL (BTUH)	EAT (°F)	LAT (°F)	CAPACITY (BTUH)	V/HZ/PH	MCA/MOCP	REMARKS
VRF-1	BREAK ROOM 111	CARRIER (NO EXCEPTIONS)	MMU-UP0181HP-UL	550	60	80.0/67.0	9013	12675	70.0	87.6	10469	208-230/60/1	1 / 15	1, 4, 5
VRF-2	TRAINING CORR. 109	CARRIER (NO EXCEPTIONS)	MMU-UP0091YHP-UL	305	60	80.0/67.0	4999	6689	70.0	87.6	5496	208-230/60/1	0.4 / 15	2, 4, 5
VRF-3A	TRAINING ROOM 110	CARRIER (NO EXCEPTIONS)	MMU-UP0181HP-UL	550	60	80.0/67.0	9013	12675	70.0	87.6	10469	208-230/60/1	1 / 15	1, 4, 5
VRF-3B	TRAINING ROOM 110	CARRIER (NO EXCEPTIONS)	MMU-UP0181HP-UL	550	60	80.0/67.0	9013	12675	70.0	87.6	10469	208-230/60/1	1 / 15	1, 4, 5
VRF-4	OPEN 107	CARRIER (NO EXCEPTIONS)	MMU-UP0071HP-UL	470	60	80.0/67.0	4084	5281	70.0	78.8	4449	208-230/60/1	0.8 / 15	1, 4, 5
VRF-5	OFFICE MGR. 106	CARRIER (NO EXCEPTIONS)	MMU-UP0071MH-UL	320	60	80.0/67.0	4330	5281	70.0	82.9	4449	208-230/60/1	0.5 / 15	1, 4, 5
VRF-6	SCM 105	CARRIER (NO EXCEPTIONS)	MMU-UP0071HP-UL	470	60	80.0/67.0	4084	5281	70.0	78.8	4449	208-230/60/1	0.8 / 15	1, 4, 5
VRF-7	OPEN 104	CARRIER (NO EXCEPTIONS)	MMU-UP0071HP-UL	470	60	80.0/67.0	4084	5281	70.0	78.8	4449	208-230/60/1	0.8 / 15	1, 4, 5
VRF-8	CONFERENCE 103	CARRIER (NO EXCEPTIONS)	MMU-UP0121MH-UL	350	60	80.0/67.0	6338	8449	70.0	88.7	7067	208-230/60/1	0.5 / 15	1, 4, 5
VRF-9	LOBBY 100	CARRIER (NO EXCEPTIONS)	MMU-UP0091MH-UL	340	60	80.0/67.0	5288	6689	70.0	85.0	5496	208-230/60/1	0.5 / 15	1, 4, 5
VRF-10	OPEN 121	CARRIER (NO EXCEPTIONS)	MMU-UP0071MH-UL	320	60	80.0/67.0	4330	5281	70.0	82.9	4449	208-230/60/1	0.5 / 15	1, 4, 5
VRF-11	OPEN 119	CARRIER (NO EXCEPTIONS)	MMU-UP0071MH-UL	320	60	80.0/67.0	4330	5281	70.0	82.9	4449	208-230/60/1	0.5 / 15	1, 4, 5
VRF-12	OPEN 116	CARRIER (NO EXCEPTIONS)	MMU-UP0071MH-UL	320	60	80.0/67.0	4330	5281	70.0	82.9	4449	208-230/60/1	0.5 / 15	1, 4, 5
VRF-13	STORAGE / OPEN 115	CARRIER (NO EXCEPTIONS)	MMU-UP0071MH-UL	320	60	80.0/67.0	4330	5281	70.0	82.9	4449	208-230/60/1	0.5 / 15	1, 4, 5
VRF-14	STORAGE 114	CARRIER (NO EXCEPTIONS)	MMU-UP0091MH-UL	340	60	80.0/67.0	5288	6689	70.0	85.0	5496	208-230/60/1	0.5 / 15	1, 4, 5
VRF-15	WOMEN 113	CARRIER (NO EXCEPTIONS)	MMU-UP0071MH-UL	320	60	80.0/67.0	4330	5281	70.0	82.9	4449	208-230/60/1	0.5 / 15	1, 4, 5
VRF-16	MEN 112	CARRIER (NO EXCEPTIONS)	MMU-UP0071MH-UL	320	60	80.0/67.0	4330	5281	70.0	82.9	4449	208-230/60/1	0.5 / 15	1, 4, 5
VRF-17	SETTLEMENT 118	CARRIER (NO EXCEPTIONS)	MMU-UP0151MH-UL	390	60	80.0/67.0	7916	10843	70.0	91.2	8899	208-230/60/1	0.6 / 15	1, 4, 5
VRF-18	RPA 120	CARRIER (NO EXCEPTIONS)	MMU-UP0121MH-UL	350	60	80.0/67.0	6338	8449	70.0	88.7	7067	208-230/60/1	0.5 / 15	1, 4, 5
VRF-19	IT ROOM 122	CARRIER (NO EXCEPTIONS)	MMK-UP0151HP-UL	495	60	80.0/67.0	8167	10843	70.0	86.7	8899	208-230/60/1	0.4 / 15	3, 4, 5
VRF-20A	ADMIN AREA 101	CARRIER (NO EXCEPTIONS)	MMU-UP0151HP-UL	550	60	80.0/67.0	8449	10843	70.0	85.0	8899	208-230/60/1	1 / 15	1, 4, 5
VRF-20B	OPEN OFFICE 102	CARRIER (NO EXCEPTIONS)	MMU-UP0151HP-UL	550	60	80.0/67.0	8449	10843	70.0	85.0	8899	208-230/60/1	1 / 15	1, 4, 5
VRF-20C	OPEN OFFICE 102	CARRIER (NO EXCEPTIONS)	MMU-UP0151HP-UL	550	60	80.0/67.0	8449	10843	70.0	85.0	8899	208-230/60/1	1 / 15	1, 4, 5

NOTES:
1. 4-WAY MINI CASSETTE STYLE.
2. SINGLE-DIRECTION MINI CASSETTE STYLE.
3. HIGH-WALL STYLE; COOLING-ONLY UNIT.
4. PROVIDE BACNET CONTROLS WITH I-VU CAPABILITY.
5. EQUIPMENT WILL BE FURNISHED BY OWNER. THE CONTRACTOR SHALL ASSUME OWNERSHIP OF THE EQUIPMENT AS A PART OF THE CONTRACT INCLUDING POSSESSION ON SITE, HANDLING, STORAGE, INSTALLATION, STARTUP, AND WARRANTY.

LOUVER SCHEDULE — EL/IL

GENERAL				PERFORMANCE DATA			UNIT DATA						
EQ. TAG	SERVICE	MFR	MODEL	AIR FLOW (CFM)	FACE VELOCITY (FPM)	PRESSURE DROP (IN. W.C.)	FREE AREA (SQFT)	H (IN.)	W (IN.)	FINISH / COLOR	MATERIAL	CONTROLS	REMARKS
EL-1	WAREHOUSE	GREENHECK	EHH-401	4000	434	0.03	9.2	48	66	COLOR MATCH WALL PANEL	ALUMINUM	-	1, 2, 3
EL-2	WAREHOUSE	GREENHECK	EHH-401	4000	434	0.03	9.2	48	66	COLOR MATCH WALL PANEL	ALUMINUM	-	1, 2, 3
EL-3	WAREHOUSE	GREENHECK	EHH-401	4000	434	0.03	9.2	48	66	COLOR MATCH WALL PANEL	ALUMINUM	-	1, 2, 3
EL-4	FLEET	GREENHECK	EHH-601	1650	423	0.04	3.9	36	36	COLOR MATCH WALL PANEL	ALUMINUM	-	1, 2, 3
IL-1	WAREHOUSE	GREENHECK	EHH-401	4000	434	0.03	9.2	48	66	COLOR MATCH WALL PANEL	ALUMINUM	INTERLOCKED WITH EF-2; 2-POSITION ACTUATOR; 120V; FAIL CLOSE	1, 2, 3, 4
IL-2	WAREHOUSE	GREENHECK	EHH-401	4000	434	0.03	9.2	48	66	COLOR MATCH WALL PANEL	ALUMINUM	INTERLOCKED WITH EF-3; 2-POSITION ACTUATOR; 120V; FAIL CLOSE	1, 2, 3, 4
IL-3	WAREHOUSE	GREENHECK	EHH-401	4000	434	0.03	9.2	48	66	COLOR MATCH WALL PANEL	ALUMINUM	INTERLOCKED WITH EF-4; 2-POSITION ACTUATOR; 120V; FAIL CLOSE	1, 2, 3, 4
IL-4	CAMBRIGDE HEATER	GREENHECK	EHH-401	1200	446	0.04	2.7	36	28	COLOR MATCH WALL PANEL	ALUMINUM	-	1, 2, 3
IL-5	CAMBRIGDE HEATER	GREENHECK	EHH-401	1200	446	0.04	2.7	36	28	COLOR MATCH WALL PANEL	ALUMINUM	-	1, 2, 3
IL-6	FLEET / VENDING OFFICES	GREENHECK	EHH-601	109	423	0.04	0.2	12	12	COLOR MATCH WALL PANEL	ALUMINUM	INTERLOCKED WITH SF-1; 2-POSITION ACTUATOR; 120V; FAIL CLOSE	1, 2, 3, 4
IL-7	FLEET	GREENHECK	EHH-601	1650	423	0.04	3.9	36	36	COLOR MATCH WALL PANEL	ALUMINUM	INTERLOCKED WITH EF-6; 2-POSITION ACTUATOR; 120V; FAIL CLOSE	1, 2, 3, 4

NOTES:
1. WIND-DRIVEN RAIN RESISTANT STATIONARY LOUVER.
2. HORIZONTAL BLADE CONSTRUCTION W/ DRAINABLE HEAD.
3. ALUMINUM BIRD SCREEN.
4. WASHABLE AND RESUABLE MERV-8 FILTER. SMITH FILTER CO. OR EQUAL.

THIS DRAWING IS THE PROPERTY OF DG ARCHITECTURAL AND ENGINEERING FACILITY SOLUTIONS, PLLC AND SHALL NOT BE REPRODUCED, COPIED, LENT OR ALTERED DIRECTLY OR INDIRECTLY NOR USED FOR ANY PURPOSE OTHER THAN THAT FOR WHICH IT IS SPECIFICALLY FURNISHED AND MUST BE RETURNED TO DG ARCHITECTURAL AND ENGINEERING FACILITY SOLUTIONS, PLLC ON COMPLETION OF WORK, IF REQUESTED.

DATE PLOTTED:8/11/2023 11:51:47 AM

DG Design Group
DG ARCHITECTURAL AND ENGINEERING FACILITY SOLUTIONS, PLLC
1075 WINDWARD RIDGE PKWY, STE 100, ALPHARETTA, GA 30005
PHONE: (770) 667-6250 FAX: (770) 667-6251

REVISION:	BY	DATE
1	KCC	08/11/2023


ISSUED FOR CONSTRUCTION

Coca-Cola Bottling Co. United

CLIENT: COCA-COLA BOTTLING CO. UNITED, INC.
BIRMINGHAM, AL

PROJECT: NEW MCCOMB SALES CENTER
MCCOMB, MS

DRAWING TITLE: MECHANICAL SCHEDULES



PROJECT NO. 2102482
ISSUED 08/11/23
SCALE AS NOTED
DRAWN BY KCC

DRAWING NO.
M4.01

© 2022 DG ARCHITECTURAL AND ENGINEERING FACILITY SOLUTIONS, PLLC

THIS DRAWING IS THE PROPERTY OF DG ARCHITECTURAL AND ENGINEERING FACILITY SOLUTIONS, PLLC AND SHALL NOT BE REPRODUCED, COPIED, LENT OR ALTERED DIRECTLY OR INDIRECTLY NOR USED FOR ANY PURPOSE OTHER THAN FOR WHICH IT IS SPECIFICALLY FURNISHED AND MUST BE RETURNED TO DG ARCHITECTURAL AND ENGINEERING FACILITY SOLUTIONS, PLLC ON COMPLETION OF WORK, IF REQUESTED.

VRF HEAT RECOVERY FS UNITS SCHEDULE (PURCHASED BY OWNER) — FS

GENERAL				UNIT DATA					ELECTRICAL		
EQ. TAG	EQUIPMENT SERVED	MFR	MODEL	L (IN.)	W (IN.)	H (IN.)	WT (LB.)	OPERATING SOUND LEVEL (DBA)	V/HZ/PH	MCA/MOCP	REMARKS
FS-1	SSCU-3	CARRIER	RBM-Y0383FUL	6.3	9.77	7.49	13	39	208-230/1/60	0.3 / 15	1, 3, 4, 7
FS-2	SSCU-3	CARRIER	RBM-Y0611F6PUL	22.4	41.6	8.5	117	39	208-230/1/60	1 / 15	2, 3, 4, 6, 7
FS-3	SSCU-3	CARRIER	RBM-Y0611F4PUL	22.4	28.8	8.5	84	39	208-230/1/60	0.7 / 15	2, 3, 4, 5, 7
FS-4	SSCU-3	CARRIER	RBM-Y0611F6PUL	22.4	41.6	8.5	117	39	208-230/1/60	1 / 15	2, 3, 4, 6, 7
FS-5	SSCU-3	CARRIER	RBM-Y0611F6PUL	22.4	41.6	8.5	117	39	208-230/1/60	1 / 15	2, 3, 4, 6, 7

NOTES:
1. SINGLE PORT FLOW SELECTOR UNIT FOR HEAT RECOVERY.
2. MULTI-PORT FLOW SELECTOR UNIT FOR HEAT RECOVERY.
3. R410A REFRIGERANT.
4. MAXIMUM CAPACITY PER BRANCH: 54 MBH.
5. 4 PORT VARIANT.
6. 6 PORT VARIANT.
7. EQUIPMENT WILL BE FURNISHED BY OWNER. THE CONTRACTOR SHALL ASSUME OWNERSHIP OF THE EQUIPMENT AS A PART OF THE CONTRACT INCLUDING POSSESSION ON SITE, HANDLING, STORAGE, INSTALLATION, STARTUP, AND WARRANTY.

UNIT HEATER SCHEDULE (ELECTRIC) — EUH

GENERAL				HEATING		ELECTRICAL				
EQ. TAG	SERVICE	MFR	MODEL	EAT (°F)	HEATING CAPACITY (KW)	FAN POWER (HP)	DISC.	V/HZ/PH	CONTROLS	REMARKS
EUH-1	FLEET MAINTENANCE	MODINE	HER50	40	5	1/40	BY MFR	460/60/3	NOTE 5	1, 2, 3, 4
EUH-2	FLEET MAINTENANCE	MODINE	HER50	40	5	1/40	BY MFR	460/60/3	NOTE 5	1, 2, 3, 4

NOTES:
1. COLUMN MOUNTING BRACKET.
2. MAXIMUM THROW 12'.
3. MOUNTING HEIGHT OF 12'-0" AFF.
4. DIMENSIONS: 17.3"L X 14.3"W X 17.5"H; 34LB
5. UNIT-MOUNTED THERMOSTAT; 40°F SETPOINT; SUMMER-WINTER SWITCH (MAX RATING 10A AT 250V).

ROOM NAME	CLASSIFICATION	AREA (SQFT)	AREA OA RATE (CFM/SQFT)	OCCUPANCY (# OF PEOPLE)	PEOPLE OA RATE (CFM/PERSON)	OA REQUIRED (CFM)	ACTUAL OA (CFM)	FLUSHABLE FIXTURE QUANTITY	EA REQUIRED (CFM)	ACTUAL EA (CFM)	NET POSITIVE OA (CFM)
100 - LOBBY	CORRIDOR	106	0.06	0	0.0	6	25	0	0	0	25
101 - ADMIN AREA	OFFICE SPACE	244	0.06	2	5.0	25	40	0	0	0	40
102 - OPEN OFFICE	OFFICE SPACE	895	0.06	10	5.0	104	120	0	0	0	120
103 - CONFERENCE	CONFERENCE	215	0.06	8	5.0	53	65	0	0	0	65
104 - OPEN	OFFICE SPACE	108	0.06	1	5.0	11	25	0	0	0	25
105 - SCM	OFFICE SPACE	184	0.06	1	5.0	16	25	0	0	0	25
106 - OFFICE MANAGER	OFFICE SPACE	103	0.06	1	5.0	11	25	0	0	0	25
107 - OPEN	OFFICE SPACE	103	0.06	1	5.0	11	25	0	0	0	25
108 - MAIL / COPY	TELEPHONE CL.	108	0	0	0.0	0	0	0	0	0	0
109 - TRAINING CORRIDOR	CORRIDOR	481	0.06	0	0.0	29	100	0	0	0	100
110 - TRAINING ROOM	CONFERENCE	794	0.06	28	5.0	188	200	0	0	0	200
111 - BREAK ROOM	BREAK ROOM	384	0.06	14	5.0	93	150	0	100	100	50
112 - MENS	TOILET	183	0	0	0.0	0	0	3	225	225	-225
113 - WOMENS	TOILET	177	0	0	0.0	0	0	3	225	225	-225
114 - STORAGE	OCC. STORAGE	167	0.06	1	5.0	15	25	0	0	0	25
115 - OPEN	OFFICE SPACE	112	0.06	1	5.0	12	25	0	0	0	25
116 - OPEN	OFFICE SPACE	113	0.06	1	5.0	12	25	0	0	0	25
117 - OFFICE CORRIDOR	CORRIDOR	247	0.06	0	0.0	15	25	0	0	0	25
118 - SETTLEMENT	OFFICE SPACE	203	0.06	1	5.0	17	25	0	0	0	25
119 - OPEN	OFFICE SPACE	111	0.06	1	5.0	12	25	0	0	0	25
120 - RPA	OFFICE SPACE	168	0.06	1	5.0	15	25	0	0	0	25
121 - OPEN	OFFICE SPACE	113	0.06	1	5.0	12	25	0	0	0	25
122 - IT	TELEPHONE CL.	58	0	0	0.0	0	0	0	0	0	0
						656	1000		550	550	450

HANGING FAN SCHEDULE — HVLS/PF

GENERAL				UNIT DATA				ELECTRICAL			
EQ. TAG	SERVICE	MFR	MODEL	DIAMETER	WT (LB.)	FAN SPEED (RPM)	MOTOR POWER (HP)	DISCONNECT	V/HZ/PH	CONTROLS	REMARKS
HVLS-1	FLEET MAINT.	BIG ASS FANS	PFX3-12	12'	245	139 MAX.	1.5	NOTE 5	460/60/3	NOTE 7	1 THRU 8
HVLS-2	WAREHOUSE	BIG ASS FANS	PFX3-16	16'	264	99 MAX.	1.5	NOTE 5	460/60/3	NOTE 7	1 THRU 8
HVLS-3	WAREHOUSE	BIG ASS FANS	PFX3-16	16'	264	99 MAX.	1.5	NOTE 5	460/60/3	NOTE 7	1 THRU 8
HVLS-4	WAREHOUSE	BIG ASS FANS	PFX3-16	16'	264	99 MAX.	1.5	NOTE 5	460/60/3	NOTE 7	1 THRU 8
HVLS-5	WAREHOUSE	BIG ASS FANS	PFX3-16	16'	264	99 MAX.	1.5	NOTE 5	460/60/3	NOTE 7	1 THRU 8
PF	FLEET MAINT.	BIG ASS FANS	AIREYE	30"	45	1280 MAX.	1.5	NOTE 10	120/60/1	LOCAL CONTROL	9 THRU 11
PF-2	FLEET MAINT.	BIG ASS FANS	AIREYE	30"	45	1280 MAX.	1.5	NOTE 10	120/60/1	LOCAL CONTROL	9 THRU 11
PF-3	VENDING REPAIR	BIG ASS FANS	AIREYE	30"	45	1280 MAX.	1.5	NOTE 10	120/60/1	LOCAL CONTROL	9 THRU 11
PF-4	VENDING REPAIR	BIG ASS FANS	AIREYE	30"	45	1280 MAX.	1.5	NOTE 10	120/60/1	LOCAL CONTROL	9 THRU 11

NOTES:
1. HIGH-VOLUME LOW-SPEED FAN WITH 8 AIRFOIL BLADES.
2. ONBOARD VFD.
3. MOUNTING KIT PROVIDED BY MANUFACTURER.
4. CONTROL WIRING FROM FAN TO BAFCON BY M.C.
5. NEMA L16-20P PLUG AND CORD BY MANUFACTURER.
6. FAN SHALL BE INTERLOCKED WITH FIRE SUPPRESSION SYSTEM TO SHUT DOWN FAN UPON FIRE ALARM.
7. COLUMN-MOUNTED BAFCON CONTROLLER IN SPACE AT 15 FEET AFF.
9. PERSONNEL FAN WITH 3 STEEL BLADES.
10. 16' CORD WITH STANDARD PLUG.
11. PROVIDE WITH I-BEAM / C-CHANNEL MOUTING KIT.

REGISTER, GRILLE, & DIFFUSER SCHEDULE

EQ. TAG	SERVICE	MFR	MODEL	MATERIAL	FINISH / COLOR	FACE SIZE	DAMPER TYPE	ACCESSORIES
A	LAY-IN SUPPLY GRILLE	TITUS	TMS	STEEL	BAKED ENAMEL / WHITE	24" X 24" OR 12" X 12"	NONE	BLOW CLIP AS INDICATED, PROVIDE FLEXRIGHT BRACE OR EQUAL FOR FLEX DUCT
B	CEILING RETURN / EXHAUST / TRANSFER GRILLE	TITUS	PAR	STEEL	BAKED ENAMEL / WHITE	24" X 24" OR 12" X 12"	NONE	ROUND CONNECTION, PROVIDE FLEXRIGHT BRACE OR EQUAL FOR FLEX DUCT
C	LAY-IN RETURN / EXHAUST / TRANSFER GRILLE	TITUS	PAR	STEEL	BAKED ENAMEL / WHITE	24" X 24" OR 12" X 12"	NONE	SQUARE CONNECTION

NOTES:

1. REFER TO DRAWINGS FOR APPLICABLE RGD DESIGNATIONS AND DUCT CONNECTION SIZES. ALL DESIGNATIONS MAY NOT BE USED ON THIS PROJECT.
2. SELECT BORDER TYPE TO MATCH CEILING OR WALL CONSTRUCTION. GRILLES AND DIFFUSERS INSTALLED WITHIN SUSPENDED ACOUSTICAL CEILINGS SHALL BE LAY-IN BORDER WITH MATCHING PANEL. SURFACE MOUNTING IS PERMITTED WHERE SPACE CONSTRAINTS DO NOT ALLOW FOR INSTALLATION OF LAY-IN BORDER.
3. PROVIDE MATCHING T-BAR FRAME, RETAINING CLIPS, ETC. AS REQUIRED FOR INSTALLATION.
4. LAY-IN GRILLES AND DIFFUSERS SHALL BE SUPPORTED INDEPENDENTLY OF THE T-BAR CEILING GRID.
5. DIFFUSER BLOW DIRECTIONS SHALL BE AS SHOWN ON DRAWINGS.
6. STATIC PRESSURE DROP SHALL NOT EXCEED 0.10 IN. W.C. AT DESIGN AIRFLOW; RGD CRITERIA SHALL NOT EXCEED NC 30 AT DESIGN AIRFLOW.
7. FIELD INSULATE SURFACES OF CEILING MOUNTED DIFFUSERS WITHIN CEILING CAVITIES USING REFLECTIX R6.0 INSULATION.
8. RUNOUT SIZE SHALL EQUAL DIFFUSER NECK SIZE UNLESS INDICATED OTHERWISE IN THE PLANS.

UNIT HEATER SCHEDULE (GAS) — GUH

GENERAL				HEATING DATA						UNIT DATA				ELECTRICAL DATA				
EQ. TAG	SERVICE	MFR	MODEL	EAT (°F)	LAT (°F)	HEATING OUTPUT (MBH)	HEATING INPUT (MBH)	GAS BURNER MIN. EFF.	INLET GAS PRESSURE (PSI)	L (IN.)	W (IN.)	H (IN.)	WT (LB.)	DISC.	V/HZ/PH	MCA/ MOCP	CONTROLS	REMARKS
GUH-1	WAREHOUSE	CAMBRIDGE AIR SOLUTIONS	SA250	23.0	160.0	230	250	92	5 MAX	55	21	21	250	BY MFR	115/60/1	12.3 / 20	NOTE 8	1 THRU 7
GUH-2	WAREHOUSE	CAMBRIDGE AIR SOLUTIONS	SA250	23.0	160.0	230	250	92	5 MAX	55	21	21	250	BY MFR	115/60/1	12.3 / 20	NOTE 8	1 THRU 7

NOTES:
1. DIRECT GAS-FIRED SPACE HEATER.
2. 115-VAC DIRECT DRIVE MOTOR.
3. PROVIDE WITH WALL COLLAR.
4. TWO POSITION MOTORIZED INLET DAMPER KIT.
5. TWO DIRECTIONAL OUTPUT ELBOWS.
6. INLET SCREEN.
7. HIGH PRESSURE REGULATOR PROVIDED.
8. TEMPERATURE SENSOR IN SPACE.

DG Design Group
DG ARCHITECTURAL AND ENGINEERING FACILITY SOLUTIONS, PLLC
1075 WINDWARD RIDGE PKWY, STE 100, ALPHARETTA, GA 30005
PHONE: (770) 667-6250 FAX: (770) 667-6251

REVISION	DATE	BY
1	08/11/2023	ACC

ISSUED FOR CONSTRUCTION

CLIENT: COCA-COLA BOTTLING CO. UNITED, INC. BIRMINGHAM, AL
PROJECT: NEW MCCOMB SALES CENTER MCCOMB, MS
DRAWING TITLE: MECHANICAL SCHEDULES


PROJECT NO. 2102482
ISSUED 08/11/23
SCALE AS NOTED
DRAWN BY Author

DRAWING NO.
M4.02

© 2022 DG ARCHITECTURAL AND ENGINEERING FACILITY SOLUTIONS, PLLC


DATE PLOTTED:8/11/2023 11:51:48 AM

THIS DRAWING IS THE PROPERTY OF DG ARCHITECTURAL AND ENGINEERING FACILITY SOLUTIONS, PLLC AND SHALL NOT BE REPRODUCED, COPIED, LENT OR ALTERED DIRECTLY OR INDIRECTLY NOR USED FOR ANY PURPOSE OTHER THAN FOR WHICH IT IS SPECIFICALLY FURNISHED AND MUST BE RETURNED TO DG ARCHITECTURAL AND ENGINEERING FACILITY SOLUTIONS, PLLC ON COMPLETION OF WORK, IF REQUESTED.




NOTES:
1. CARRYING WEIGHT SHALL NOT EXCEED 500#.
2. SUSPENDED PIPE SIZE SHALL NOT EXCEED 6"ø.

1 M5.01 BEAM HANGER DETAIL - 500#
NTS




NOTES:
1. CARRYING WEIGHT SHALL NOT EXCEED 1000#.
2. SUSPENDED PIPE SIZE SHALL NOT EXCEED 10"ø.
3. SIZE HANGER RODS FOR APPLIED LOADS WITH A SAFETY FACTOR OF THREE(3), MINIMUM ROD SIZE 3/8"ø.
4. SEE STRUCTURAL DRAWINGS FOR ADDITIONAL SEISMIC HANGER AND/OR BRACING REQUIREMENTS, MODIFY THAT SHOWN ACCORDINGLY.

2 M5.01 JOIST HANGER ANGLE DETAIL - 1000#
NTS



NOTES:
1. CARRYING WEIGHT SHALL NOT EXCEED 500#.
2. SUSPENDED PIPE SIZE SHALL NOT EXCEED 6"ø.
3. LOCATE WITHIN 6" OF JOIST PANEL POINT OR INSTALL ADDITIONAL JOIST REINFORCEMENT.
4. HANG LOAD CONCENTRICALLY.
5. SEE STRUCTURAL DRAWINGS FOR ADDITIONAL SEISMIC HANGER AND/OR BRACING REQUIREMENTS, MODIFY THAT SHOWN ACCORDINGLY.

3 M5.01 JOIST HANGER ANGLE DETAIL - 500#
NTS




HANGER SCHEDULE

L4x4x1/4	MAXIMUM ALLOWED JOIST SPACING 4'-0" ON CENTER, MAXIMUM LOAD 1000#. SUSPENDED PIPE SIZE SHALL NOT EXCEED 10"ø.
L4x4x3/8	MAXIMUM ALLOWED JOIST SPACING 6'-0" ON CENTER, MAXIMUM LOAD 1000#. SUSPENDED PIPE SIZE SHALL NOT EXCEED 10"ø.
(2)L4x4x1/4	MAXIMUM ALLOWED JOIST SPACING 6'-0" ON CENTER, MAXIMUM LOAD 1500#. ALL FASTENERS AND HANGER RODS SHALL BE LOCATED BETWEEN ANGLE LEGS AS SHOWN. SUSPENDED PIPE SIZE SHALL NOT EXCEED 14"ø.


NOTES:
1. ANGLE HANGERS CARRYING WEIGHT LESS THAN 1000# SHALL BE CONSTRUCTED AS SCHEDULED OR SUBMITTED TO THE ENGINEER FOR APPROVAL.
2. SUSPENDED PIPE SIZES SHALL NOT EXCEED SCHEDULED SPECIFICATIONS.
3. SIZE HANGER RODS FOR APPLIED LOADS WITH A SAFETY FACTOR OF THREE (3), MINIMUM ROD SIZE 3/8"ø.

4 M5.01 JOIST HANGER ANGLE DETAIL - SPAN
NTS




NOTES:
1. CARRYING WEIGHT SHALL NOT EXCEED 150# PER THROUGH BOLT.
2. FURNISH EQUIPMENT DISCONNECT AS SCHEDULED, COORDINATE WITH ELECTRICAL CONTRACTOR AS REQUIRED.


5 M5.01 ELECTRIC UNIT HEATER MOUNTING
NTS



6 M5.01 SIDEWALL EXHAUST FAN DETAIL
NTS




7 M5.01 DUCTED STATIONARY LOUVER DETAIL
NTS




NOTE:
COORDINATE TRANSFER AIR DUCT WALL PENETRATION REQUIREMENTS WITH THE GENERAL CONTRACTOR.

8 M5.01 TRANSFER WALL PENETRATION DETAIL
NTS




9 M5.01 METAL PIPE WALL PENETRATION DETAIL
NTS




NOTES:
1. MECHANICAL CONTRACTOR RESPONSIBLE TO CONFIRM PROPER METERING DEVICE (PISTON ORIFICE) HAS BEEN INSTALLED/SUPPLIED BY THE EQUIPMENT MANUFACTURER. VERIFY SYSTEM SUPERHEAT AND SUB-COOLING PERFORMANCE; ADJUST REFRIGERANT CHARGE AS REQUIRED.
2. ATC RESPONSIBLE FOR ALL CONTROL COMPONENTS REQUIRED TO SATISFY THE SPECIFIED EQUIPMENT CONTROL SEQUENCE OF OPERATION INCLUDING, BUT NOT LIMITED TO, WIRING BETWEEN EQUIPMENT COMPONENTS AND THE SPACE THERMOSTAT.
3. COORDINATE INSTALLATION SCHEDULE WITH CONSTRUCTION MANAGER AND IMP CONTRACTOR.

10 M5.01 SPLIT SYSTEM DETAIL - CASSETTE



NOTES:
1. FIELD COORDINATE ALL DUCTWORK ROUTING AND ELEVATIONS WITH ALL TRADES PRIOR TO CONSTRUCTION. NOTIFY THE CONSTRUCTION MANAGER AND ENGINEER OF ANY CONFLICTS REQUIRING SIGNIFICANT RELOCATION OR MODIFICATION.
2. EXTERNAL DUCT INSULATION SHALL BE APPLIED IN ADDITION TO ANY INTERNAL INSULATION LINER SHOWN ON THE DRAWINGS.
3. LAY-IN TYPE CEILING DIFFUSERS AND REGISTERS SHALL BE SUPPORTED BY THE CEILING GRID. SEE MANUFACTURER'S GUIDELINES FOR PERMANENT CEILING INSTALLATION REQUIREMENTS.

11 M5.01 TYPICAL ROUND DUCT TAKE-OFF DETAIL
NTS



NOTES:
1. FIELD COORDINATE ALL DUCTWORK ROUTING AND ELEVATIONS WITH ALL TRADES PRIOR TO CONSTRUCTION. NOTIFY THE CONSTRUCTION MANAGER AND ENGINEER OF ANY CONFLICTS REQUIRING SIGNIFICANT RELOCATION OR MODIFICATION.
2. EXTERNAL DUCT INSULATION SHALL BE APPLIED IN ADDITION TO ANY INTERNAL INSULATION LINER SHOWN ON THE DRAWINGS.

12 M5.01 TYPICAL RECTANGULAR DUCT TAKE-OFF DETAIL
NTS

DG Design Group
DG ARCHITECTURAL AND ENGINEERING FACILITY SOLUTIONS, PLLC
1075 WINDWARD RIDGE PKWY, STE 100, ALPHARETTA, GA 30005
PHONE: (770) 667-6250 FAX: (770) 667-6251


REVISION	BY	DATE
ISSUED FOR CONSTRUCTION	KCC	08/11/2023

CLIENT: COCA-COLA BOTTLING CO. UNITED, INC. BIRMINGHAM, AL
PROJECT: NEW MCCOMB SALES CENTER MCCOMB, MS
DRAWING TITLE: MECHANICAL DETAILS




PROJECT NO. 2102482
ISSUED 08/11/23
SCALE AS NOTED
DRAWN BY KCC
DRAWING NO. M5.01

© 2022 DG ARCHITECTURAL AND ENGINEERING FACILITY SOLUTIONS, PLLC




NOTES:
1. FAN MUST BE MOUNTED IN A LOCATION THAT ALLOWS MINIMUM OF 1'-0" CLEARANCE BETWEEN THE FAN BLADES AND ANY OBSTRUCTIONS AND ALLOWS THE BOLTS SECURING THE ANGLE IRONS TO THE JOIST BEAM TO BE APPROPRIATELY FASTENED. MECHANICAL CONTRACTOR TO COORDINATE FINAL LOCATION WITH SPRINKLER CONTRACTOR.
2. THIS INSTALLATION METHOD IS ONLY TO BE USED WHEN INSTALLING THE FAN FROM ANGLE IRONS SECURED TO THE UPPER JOIST BEAM. FOR ALL OTHER METHODS, REFER TO MANUFACTURER'S INSTRUCTIONS.
3. ALL BOLTS, WASHERS, NUTS, AND OTHER SECURING HARDWARE MUST MEET OR EXCEED SPECIFICATIONS SET FORTH BY THE MANUFACTURER.
4. THE REDUNDANT SAFETY CABLE MUST BE PROPERLY INSTALLED AS PER THE MANUFACTURER'S SPECIFICATIONS AND INSTRUCTIONS.
5. THE WALL CONTROLLER SHALL BE MOUNTED AS PER MANUFACTURER'S INSTRUCTIONS. REFER TO ELECTRICAL DRAWINGS FOR COORDINATION.
6. ANY ADDITIONAL INTERFERENCES OR MOUNTING CONSIDERATIONS SHALL BE BROUGHT TO THE ATTENTION OF THE ENGINEER PRIOR TO INSTALLATION.
7. MECHANICAL CONTRACT TO COORDINATE FINAL FAN LOCATION WITH SPRINKLER CONTRACTOR.
8. FOR JOIST SPANS 8'-0" AND LARGER, TWO PAIRS OF ANGLE IRONS SHALL BE USED. PAIRS SHOULD BE PLACED BACK TO BACK AND FASTENED TOGETHER WITH (1) 1/2-13 BOLT, (2) 1/2" WASHERS AND (1) 1/2" NUT AS PER FAN MANUFACTURER'S INSTRUCTIONS. DO NOT USE ANGLE IRONS FOR SPANS LARGER THAN 12'-0".
9. ANGLE IRONS SHALL BE PURCHASED AND INSTALLED BY MISCELLANEOUS STEEL CONTRACTOR. COORDINATE WITH MECHANICAL CONTRACTOR AND REFER TO STRUCTURAL SPECIFICATIONS.

1 M5.02 HIGH-VOLUME LOW-SPEED FAN MOUNTING DETAIL
NTS




NOTE(S):
1. CONTROL WIRING FROM HVLS FANS TO BAFCON CONTROLLER BY MECHANICAL CONTRACTOR.
2. HVLS-3, HVLS-4, AND HVLS-5 SHALL BE CONTROLLED INDIVIDUALLY OR AS A GROUP BY THE BAFCON CONTROLLER.


2 M5.02 CONTROLS DIAGRAM - FLEET MAINT. + WAREHOUSE HVLS FANS
NTS



3 M5.02 TRANSFER DUCT THROUGH NON RATED PARTITION
NTS




4 M5.02 GAS PRESSURE REGULATING STATION DETAIL
NTS




NOTE:
1. LINE SIZES AS CALLED FOR ON SITE PLAN.

5 M5.02 GAS SERVICE WITH BY-PASS DETAIL
NTS




NOTE:
1. SEISMIC SHUT-OFF VALVES ARE OPTIONAL AND ARE NOT REQUIRED FOR NONESSENTIAL FACILITIES LOCATED WITHIN SEISMIC ZONES 1 OR 2.


6 M5.02 GAS PRESSURE REGULATOR DETAIL
NTS



7 M5.02 DUCT ROOF PENETRATION DETAIL
NTS



8 M5.02 DUCT WALL PENETRATION DETAIL
NTS




NEGATIVE STATIC PRESSURE DRAIN

POSITIVE STATIC PRESSURE DRAIN

NOTES:
1. ALL DIMENSIONS SHOWN ARE IN INCHES REFERENCED TO BOTTOM OF PIPE AND CONDENSATE DRAIN. STATIC PRESSURE IS IN INCHES OF WATER COLUMN (IN. W.C.).
2. TRAP HEIGHT CALCULATIONS ARE BASED ON THE ABSOLUTE VALUE OF STATIC PRESSURE (SP). ALL DIMENSIONS REPRESENT MINIMUM PERMISSIBLE VALUES.
3. EXTEND CONDENSATE DISCHARGE TO NEAREST ROOF DRAIN. PITCH AT 1/4 INCH PER FOOT TOWARDS ROOF DRAIN.
4. CONDENSATE TRAP SHALL BE CONSTRUCTED OF TYPE L COPPER WITH BRAZED FITTINGS.
5. TRAP SIZE SHALL MATCH EQUIPMENT CONDENSATE DRAIN CONNECTION SIZE.
6. INSULATE P-TRAPS AND CONDENSATE DRAIN PIPING AS INDICATED ON DRAWINGS.

9 M5.02 TYPICAL CONDENSATE P-TRAP DETAIL
NTS


NOTES:
1. CARRYING WEIGHT SHALL NOT EXCEED 200#.
2. CONTRACTOR RESPONSIBLE TO PROVIDE SUPPORT SPACING AS REQUIRED TO LIMIT THE APPLIED LOAD ON EACH INDIVIDUAL SUPPORT AS NOTED. MAXIMUM SUPPORT SPACING FOR TYPE AND SIZE OF PIPING/CONDUIT SHALL BE AS SPECIFIED.
3. ALL PIPING/CONDUIT SHALL BE SUPPORTED IN THE HORIZONTAL RUN. 1'-0" MAXIMUM PRIOR TO THE DROP
4. IF PIPE INSULATION AND JACKET ARE REQUIRED AS SPECIFIED. THE JACKET SHALL COVER THE SPLIT RING CLAMP. SILICONE CHALK (COLOR MATCHING JACKET) SHALL BE USED TO SEAL THE JACKET AROUND THE PIPE CLAMP.



WALL FASTENER SCHEDULE

WALL TYPE	FASTENER TYPE	FASTENER SIZE	EMBEDMENT
CONCRETE	TAPCON PHILLIPS SCREW	3/16"x2 3/4"	2 1/2" MINIMUM
CMU	TAPCON PHILLIPS SCREW	3/16"x1 3/4"	1 1/2" MINIMUM
IMP	FAB-LOC HEX SCREW	10-4	1" MINIMUM
STUD GYPSUM	WOOD PHILLIPS SCREW	#12-11x2 1/2"	2" MINIMUM
NOTE: FASTENER MATERIAL SHALL MATCH SUPPORT MATERIAL SPECIFIED.			

10 M5.02 FABRICATED WALL SUPPORT DETAIL
NTS



11 M5.02 ROOF EXHAUST HOOD/CURB DETAIL
NTS

THIS DRAWING IS THE PROPERTY OF DG ARCHITECTURAL AND ENGINEERING FACILITY SOLUTIONS, PLLC AND SHALL NOT BE REPRODUCED, COPIED, LENT OR ALTERED DIRECTLY OR INDIRECTLY NOR USED FOR ANY PURPOSE OTHER THAN THAT FOR WHICH IT IS SPECIFICALLY FURNISHED AND MUST BE RETURNED TO DG ARCHITECTURAL AND ENGINEERING FACILITY SOLUTIONS, PLLC ON COMPLETION OF WORK, IF REQUESTED.

DG Design Group
DG ARCHITECTURAL AND ENGINEERING FACILITY SOLUTIONS, PLLC
1075 WINDWARD RIDGE PKWY, STE 100, ALPHARETTA, GA 30005
PHONE: (770) 667-6250 FAX: (770) 667-6251

REVISION	BY	DATE
1 ISSUED FOR CONSTRUCTION	KCC	08/11/2023

Coca-Cola Bottling Company United

CLIENT: COCA-COLA BOTTLING CO. UNITED, INC. BIRMINGHAM, AL
PROJECT: NEW MCCOMB SALES CENTER MCCOMB, MS
DRAWING TITLE: MECHANICAL DETAILS

KEVIN C. HAGGEN, 34021, REGISTERED PROFESSIONAL ENGINEER, STATE OF MISSISSIPPI

PROJECT NO. 2102482
ISSUED 08/11/23
SCALE AS NOTED
DRAWN BY KCC
DRAWING NO. M5.02

© 2022 DG ARCHITECTURAL AND ENGINEERING FACILITY SOLUTIONS, PLLC

DATE PLOTTED:8/11/2023 11:51:50 AM